

B
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kaiser-Francis

Complete Address 4120 E. 51st St., Tulsa, Oklahoma 74135

Lease Name Cramm Well No. 5

Location SW NW SW Sec. 15 Twp. 19 Rge. 9 (E) (W) X

County Rice Total Depth 3222'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 5 PM Day 10 Month December Year 1970

The above well was plugged as follows:

5 1/2" plug pushed to 2950'. Hole filled with sand to 2900' and cemented with 5 sacks
cement. Hole filled with mud to 210'. Rock bridge set from 210' to 200' and hole
cemented with 35 sacks cement. Hole filled with mud to 40'. Rock bridge set from
40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 12/14/70
INV. NO. 3049-W

Signed: *William D. Loman*
Well Plugging Supervisor