

15.135.202450000

Form CP-3  
Rev. 6-26-62

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address: P. O. Box 398 Ness City, Kansas

Lease Name Thompson Well No. 2

Location C SW SW Sec. 29 Twp. 20 Rge. 24 (E) (W) XX

County Ness Total Depth 1454

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Strata Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 9:25A Day 5 Month 5 Year 1969

The Above well was plugged as follows:

RTD 1454' 8 5/8 csg set at 288' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt.  
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE \_\_\_\_\_

INV. NO. \_\_\_\_\_