

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beardmore Oil, Inc.

Complete Address 700 One Twenty Bldg., Wichita, Kansas

Lease Name Schneider Well No. 1

Location NE SW Sec. 31 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4486

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor R & W Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 11A Day 5 Month 5 Year 1970

The above well was plugged as follows:

RTD 4486' 8 5/8 csg set at 345' cwc Cmt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 330' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/6/70

INV. NO. 1853-11

Signed: [Signature]
Well Plugging Supervisor