

15-135-20249-0000

R

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address: Box 398 Ness City, Kansas 67560

Lease Name ^{ER} Frecking Well No. 2

Location C SW SE Sec. 30 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4452

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Strata Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 9P Day 17 Month 5 Year 1969

The Above well was plugged as follows:

RTD 4452 8 5/8 csg set at 288' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey
Well Plugging Supervisor

DATE 5-19-69

INV. NO. 9797-W