

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address: Box 398 Ness City, Kansas

Lease Name (FERCKING) ~~Fricking~~ "A" Well No. 1

Location C NW NE Sec. 30 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4475

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Strata Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 3:20P Day 23 Month 4 Year 1969

The Above well was plugged as follows:

RTD 4475' 8 5/8 csg set at 286' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1969

CONSERVATION DIVISION
Wichita, Kansas

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 4/28/69

INV. NO. 9661-W