

15.135-20082-0000

Form CP-3
Rev. 6-26-62

K
KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name R. V. Lehner

Complete Address: Box 398 Ness City, Kansas

Lease Name Thompson Well No. 1

Location C SE SE Sec. 29 Twp. 20 Rge. 24 (E) (W) X

County Ness Total Depth 4449

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drilling Inc.

Address: Wichita, Kansas License No.

Operation Completed: Hour 7 P Day 19 Month 11 Year 1967

The Above well was plugged as follows:

RTD 4449' 8 5/8 csg set at 328' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 100 sc cem.

thru drill pipe. Heavy mud to 330' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 11/21/67

INV. NO. 6740-W