

KANSAS

Form CP-3
Rev. 6-9-67

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed July 28, 1967.

RECEIVED
AUG 14 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Mull Drilling Company, Inc.
Complete Address 1625 Wichita Plaza Bldg., Wichita, Kansas 67202
Lease Name Price Well No. # 1
Location C NW NW Sec. 2 Twp. 28 Rge. 20 (E) (W)W
County Kiowa Total Depth 5000'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated _____
Plugging Contractor Walters Drilling Company
Address 400 Insurance Bldg., Wichita, Ks. 67202 License No. _____
Operation Completed: Hour 9:00 P.M. Day 11th Month August Year 1967

The above well was plugged as follows:

510' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 195'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 300', and cemented with 25 sacks, through the drill
pipe, with cement from 300' to 225'. Hole was filled with drilling mud to
40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of
hulls on fluid at 40', and cementd with 9 sacks, with cement from 30' to
the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/14/67
INV. NO. 6118-W

Signed: Archie Elving
Well Plugging Supervisor