

State of Kansas



15-091-20004-0000

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 29 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. R. G. Smith of R. G. Smith has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: R. G. Smith,

Complete Address: 602 Rule Building, Wichita, Kansas.

Lease Name: Evans Well No. 1

Location: NE-NE-SE, Sec. 11 Twp. 16 Rge. (E)(W) 43

County: Greeley Total Depth          Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Smith was instructed to plug the well as follows:

357'--8 5/8" Surface casing, cement circulated with 360 Sx.

Circulate hole with heavy mud. Pull DP to 1575' and displace 100 Sx.  
cement thru DP. Pull DP to 370' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent