



15-071-20255-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

RECEIVED
STATE CORPORATION COMMISSION
3-2-82
MAR 2 1982

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

24 February 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-071-20255-00-00

Dear Sir:

Mr. Ron Ofterburger of Smith Cattle Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Smith Cattle Inc.

Complete Address: P.O. Box 339, Tribune Kansas 67879

Lease Name: Brunswick Well No. 13

Location: 440' FEL-330' ENL of NE 1/4 Sec. 18 Twp. 18S Rge. 39W (E) (W)

County: Greeley Total Depth: 3030'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Ofterburger was instructed to plug the well as follows:

There is 310' of 8 1/2" surface casing cement circulated. The anhydrite was topped at 1350'. 1st plug at 1280' with 50 bbl of cement. 2nd plug pushed rubber plug to 300' and pumped 35 bbl of cement on top of it. 3rd plug 40' to 0' on solid bridge with 10 bbl of cement. Then circulated 10 bbl of cement in rat hole. The cementing was pumped through drill pipe. The plugging was accomplished by Dowell Cementing with common cement with 2% gelb 3% C.C.

Very truly yours,

Paul Luthi
Conservation Division Agent