

State of Kansas



WM. H. AYERS Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Biggs of Pickrell Drlg. Co. has this date requested permission to plug the following described well:

Mr. Biggs guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bnk Bldg. Wichita, Kansas

Lease Name: Copeland "C" Well No. 1

Location: C NW SW Sec. 18 Twp. 20 Rge. 24 (E)(W) X

County Ness Total Depth 4496 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Biggs was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and
displace 30 sc cement thru drill pipe. Heavy mud to 240' set
cementing plug and displace 20 sc cement thru drill pipe. Heavy
mud to 40' set cementing plug, 1/3 sc hulls and 10 sc cement to
base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Ben Messing
Conservation Division Agent