

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Mike Hrier of Simmons Drly. Co. has this
date requested permission to plug the following described well:

Operator's Full Name: Noyager Petroleum, Inc.
Complete Address: 110-16th St. 800 Petroleum Bldg. - Denver, Colo.

Lease Name: Eynard Well No. #25-14

Location: C-SE-SW Sec. 25 Twp. 20 Rge. 24 (E) (W)

County: Wes Total Depth: 4500 ft.

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated: _____

Mr. Hrier was instructed to plug the well as follows:

8 5/8" 209^{ft} SP. cen w/160^{ft} Cement - 2% Gel. + 3% Ca-Cl.

Order 115^{ft} 50% Pozmix 6% Gel. + 8 5/8" Plug.

spot with Drill Stem - with Heavy Mud Between all Plugs.

1st Plug. @ 860^{ft} w/65^{ft} Cent.

2nd Plug. @ 300^{ft} w/30^{ft} Cent.

3rd Plug. - Solid Bridge - 40^{ft} to 10^{ft} w/10^{ft} Cent.

5^{ft} In Rat Hole

5^{ft} In Mouse Hole

Very truly yours, (By Halliburton Co.)

Marion Schmidt
Conservation Division Agent

RECEIVED
MAY 7 1981
CONSERVATION DIVISION
Wichita, Kansas