

15.135.20577-0000

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Steincamp of Strata Drlg. Inc., has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: R. V. Lehner

Complete Address: P. O. Box 398 Ness City, Kansas

Lease Name: Cranston Well No. 2

Location: C SE NE Sec. 25 Twp. 20 Rge. 24 (E)(W) X

County: Ness Total Depth 4413 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
100 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

Geo F. Massey
Conservation Division Agent