

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 7 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Strata Drlg. has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: R. V. Lehner

Complete Address: P. O. Box 398 Ness City, Ks.

Lease Name: Thompson Well No. 2

Location: G SW SW Sec. 29 Twp. 20 Rge. (E)(W) 24

County: Ness Total Depth 4454 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole
with 2 sk cmt.

Very truly yours,

Leo F. Massey
 Conservation Division Agent