

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-097-20028-000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed July 28, 1967.

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this
date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Ks. 67202

Lease Name: Price Well No. # 1

Location: C NW NW Sec. 2 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

510' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent

RECEIVED
AUG 14 1967
CONSERVATION DIVISION
WICHITA, KANSAS