

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21554-0000

LEASE NAME Honderick

WELL NUMBER #1

660 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 36 TWP. 16S RGE. 18 (X) or (W)

COUNTY Rush

Date Well Completed 05/15/91

Plugging Commenced _____

Plugging Completed 04/03/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ANR PRODUCTION

ADDRESS 9 Greenway Plaza Suite 2751

PHONE# (713) 877-7590 OPERATORS LICENSE NO. 30658

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Unsure (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Granite Wash Depth to Top 3600 Bottom 3714 T.D. 3771
Arbuckle

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Gas	3050	n/a	8 5/8"	1200'	
Heebner	unsure	3334	n/a	5 1/2"	3770'	
Lansing	unsure	3567	n/a			
Granite Wash	unsure	3286	n/a			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Spot 2 sx of cement on top of CIBP. Circulate with 9# +/- plug mud and POOH.
MIRU electric line unit and trip in hole with 3-3/8" casing perforator.
Perforate the casing at 1000 ft, 4 holes. Pull out of hole and rig down
electric line unit. Open the 8-5/8" x 5-1/2" annulus valve. Establish
(if additional description is necessary, use BACK of this form.) cover

Name of Plugging Contractor Halliburton Energy Services License No. _____

Address P.O. Box 1598, Liberal KS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANR Production

STATE OF Texas COUNTY OF Harris, ss.

Deborah Moore


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Deborah Moore

(Address) 9 Greenway Plaza Ste. 2751

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 96

My Commission Expires: July 5, 1997



circulation, mix and pump 200 sx of cement leaving 5-1/2 casing full at surface.

*All cement in Class H 65/35 pozmix with 6% gel?

Dig out cellar and remove wellhead, 5-1/2", 8-5/8" and conductor pipe to 3' below ground level. Weld abandonment plate on the 5-1/2" casing.

Restore location and remove all equipment to Coastal's Elkhart, KS yard.

8-5/8" @ 1200', cmt w/625 sx

5-1/2", # 2770', cmt w/435 sx

CIBP @ 3575'