


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ford County. Sec. 14 Twp. 26 Rge. 23 (E) (W)
Location as "NE/CNW*SW*" or footage from lines. C NW NE
Lease Owner Slawson Drilling, Inc.
Lease Name ~~XXXXXXXX~~ Bleumer Well No. B-#1
Office Address 406 One-Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-9-64 19
Application for plugging filed 11-9-64 19
Application for plugging approved 11-9-64 19
Plugging commenced 11-9-64 19
Plugging completed 11-9-64 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 5150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	357'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 700' Plug 25 sks. cement
Mud to 360' Plug 25 sks. cement
Mud to 45' 1/2 sk. hulls 15 sks. cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1964 11-17-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1964

Wanda Dinkel
Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

COMPANY: Slawson Drilling, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: BLEUMER B-#1
 LOCATION: C NW NE Sec. 14-26-23
 FORD COUNTY, KANSAS
 COMMENCED: 10-26-64
 COMPLETED: 11-9-64

0	30	Sand, Clay
30	50	Shale
50	357	Shale, Redbed
357	455	Shale
455	805	Shale, Redbed
805	845	Sand
845	955	Shale, Redbed
955	975	Anhydrite
975	1485	Shale
1485	1535	Anhydrite
1535	1890	Shale & Lime
1890	2400	Shale
2400	2425	Shale & Lime
2425	2545	Lime & Shale
2545	3375	Lime
3375	3815	Lime & Shale
3815	4889	Lime
4889	4903	Chert
4903	4976	Lime & Chert
4976	4986	Mississippi (dolomite)
4986	5128	Lime (dolomite)
5128	5150	Lime & Chert
	<u>5150</u>	<u>Rotary Total Depth - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION

NOV 17 1964

CONSERVATION DIVISION
 Wichita, Kansas

 Set 8 5/8" new casing @ 357' cemented with 300 sacks HA5 Posmix

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Bleumer B-#1 well, located C NW NE of Section 14, Township 26, Range 23, Ford County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 16th day of November, 1964.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires
 April 1, 1967