

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-05420.00.00

API NUMBER _____

LEASE NAME MEIER

WELL NUMBER 2

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 11S RGE. 18 (X) or (W)

COUNTY Ellis

Date Well Completed 4/15/54

Plugging Commenced 5/29/86

Plugging Completed 5/29/86

LEASE OPERATOR WALTERS DRILLING CO., INC.

ADDRESS 100 S. Main - Suite 420 - Wichita, Kansas 67202

PHONE# (316) 265-6683 OPERATORS LICENSE NO. 5076

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? ----

Producing Formation Arbuckle Depth to Top 3533 Bottom T.D. 3536-1/2

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	STATE CORPORATION COMMISSION 6-19-86 JUN 19 1986			8-5/8	189	None
				Squeezed	624	-----
	CONSERVATION DIVISION Wichita, Kansas			5-1/2	3534	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 100 bbls. saltwater down 5-1/2 casing to establish rate. Pumped 50 sx common cement and 200 sacks of hulls using 150 bbls. frsh water. Maximum pressure 700 psi. Used 50 sacks common cement in annular space between 5-1/2" and 8-5/8"

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Walters Drilling Co., Inc. License No. 5076

Address 100 S. Main - Suite 420 - Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Robert F. Walters (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert F. Walters

(Address) 100 S. Main - Suite 420
Wichita, Kansas 67202



ED AND SWORN TO before me this 18 day of June, 19 86

Linda L. Rushton
 Linda L. Rushton Notary Public

My Commission Expires: 10-14-89

MEIER NO. 2

Location:	NW SE NW Sec. 36-11S-18W Ellis County, Kansas	Date Spudded: 3-21-54
Operator:	Walters Drilling Co., Inc.	Rotary Completion: 4-1-54
Contractor:	Walters Drilling Co., Inc.	Elevation: 1986 Gr 1989 DF 1991 KB
Surface Casing:	8 5/8" set at 189' with 100 sacks cement and 1 Cal. Chloride	
Oil String:	5 1/2" set at 353 1/4' with 100 sacks cement	

L O G

(Figures indicate bottom of formation)

Surface	0 to 189
Shale and Shells	497
Sand and Shells	650
Shale	745
Sand	901
Shale	1241
Anhydrite	1280
Shale and Shells	2038
Shale and Lime	2150
Lime	2308
Shale and Lime	2459
Shale and Shells	2570
Shale and Lime	2766
Lime	2772
Lime and Shale	2840
Shale	2959
Lime and Shale	3036
Lime	3090
Lime and Shale	3324
Lime	3367
Shale and Lime	3534
Total Depth (Rotary)	3534

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO. INC.

By

Robert F. Walters
President

Subscribed and sworn to before me
this 2nd day of April, 1954.

Notary Public

My commission expires: March 10, 1956

STATE BOARD OF CONSERVATION
MAY 19 1985
CONSERVATION DIVISION
WICHITA, KANSAS