

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20181-00-00
Spot: SW Sec/Twnshp/Rge: 7-10S-24W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: RICHMEIER D Well #: 1
County: GRAHAM Total Vertical Depth: 3982 feet

Operator License No.: 34115
Op Name: SCHIPPERS OILFIELD SERVICES, LLC
Address: 1255 E. HWY 24
HOXIE, KS 67240

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3985		200 SX
SURF	8.625	145		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2012 3:15 PM
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC
Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: Shot perforations @ 2100', 1230' and 200'.
Ran sand pump and got to 2876'. Plugged from there.
Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2012 3:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2810' and pumped 125 sx cement w/200 # hulls.
Pulled tubing to 1716' and pumped 180 sx cement w/200 # hulls.
Pulled tubing to 1001' and pumped 215 sx cement. Good circulation of cement.
Tied on to back side and pumped 15 sx cement. Back side full.
Pulled tubing out and topped off with 15 sx cement. Hole standing full.

GPS: 39.19349, -100.04736

Perfs:

RECEIVED
OCT 12 2012
KCC WICHITA

Remarks: SOS CEMENT TICKET # 628

Plugged through: TBG

District: 04

Signed [Signature] (TECHNICIAN)

CM

Form CP-2/3

OCT 04 2012