

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-065-22097-00-00  
 Spot: E2NWSW Sec/Twnshp/Rge: 7-10S-24W  
1980 feet from S Section Line, 4290 feet from E Section Line  
 Lease Name: RICHMEIER D Well #: 3  
 County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 34115 •  
 Op Name: SCHIPPERS OILFIELD SERVICES, LLC  
 Address: 1255 E. HWY 24  
HOXIE, KS 67740

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4020		370 SX
SURF	8.625	216		85 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2012 2:00 PM  
 Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC Phone: (785) 678-2621  
 Proposal Revd. from: \_\_\_\_\_ Company: \_\_\_\_\_

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls. Bridged off at 2015'. Brought in power swivel and washed down to 2277'. Could not get any further.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 10/02/2012 11:40 AM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 2248'. Pumped 350 sx cement w/30 # hulls. Lost circulation.  
 Pulled tubing out and waited till morning.  
 Ran tubing in. Tagged cement at 1344'. Set tubing @ 1315' and pumped 150 sx cement. Good circulation of cement.  
 Pulled tubing out. Topped off w/15 sx cement.  
 Tied on to back side and squeezed w/30 sx cement. Hole standing full.  
 GPS: 39.19500, -100.04848

Perfs:			
Top	Bot	Thru	Comments
3948	3954		
3926	3930		
3908	3914		
3886	3890		
3825	3830		
3784	3788		

RECEIVED  
 OCT 12 2012  
 KCC WICHITA

Remarks: SOS CEMENT TICKET # 625 AND 627

Plugged through: TBG

District: 04

Signed *Marvin Mills* (TECHNICIAN) CM

OCT 04 2012