

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-163-23080-00-00  
 Spot: SWNWNW Sec/Twnshp/Rge: 12-9S-17W  
4288 feet from S Section Line, 4896 feet from E Section Line  
 Lease Name: BAXA Well #: 11  
 County: ROOKS Total Vertical Depth: 3486 feet

Operator License No.: 3833  
 Op Name: SHAIDA, JOHN H.  
 Address: 4126 N SWEET BAY CIR  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3482		120 SX
SURF	8.625	223		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2012 12:00 AM  
 Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
 Proposal Rcvd. from: JOHN SHAIDA Company: QUALITY OIL WELL CEMENTING Phone: (316) 304-7888

Proposed Plugging Method: DV @ 1298' w/340 sx cement.  
Production Perfs: 3157' - 3396'. Topeka & LKC  
10/02/2012 Ordered 450 sx 60/40 pozmix 4% gel cement w/7 sx gel and 500 # hulls.  
10/03/2012 Ordered 200 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS  
 Date/Time Plugging Completed: 10/03/2012 10:30 AM

Witness Type: COMPLETE (100%)  
 KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

10/02 Ran tubing and bit pushed plug to bottom @ 3375'. Pulled bit and ran tubing back to 3375'. Pumped 7 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1920' and pumped 125 sx cement. Lost circulation. Pulled tubing to 902' and pumped 100 sx cement w/200 # hulls. Shut in 30 minutes.  
 Pumped 150 sx cement with little returns. PTOH. Shut in overnight.  
 10/03 Ran tubing and tagged cement @ 900'. Pumped 90 sx cement w/200 # hulls. Cement circulated.  
 PTOH. Topped off 5 1/2" casing w/15 sx cement. Casing full. Hooked up to back side and pumped 10 sx cement. Maximum pressure 300 psi. Shut in pressure 300 psi.

**Perfs:**

Top	Bot	Thru	Comments
3396			
3371			
3347			
3337			
3327			
3320			
3274			
3260			
3248			
3214			
3196			
3157	3396		
3136			
3060			

Remarks: QUALITY OIL WELL CEMENTING

Plugged through: TBG

District: 04

Signed Richard Williams  
10/29/12 (TECHNICIAN)

CM

RECEIVED

OCT 15 2012

KCC WICHITA

OCT 08 2012