

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-28117-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 19-26S-17E
4400 feet from S Section Line, 2275 feet from E Section Line
Lease Name: S EARL GREY Well #: PDC #4
County: WOODSON Total Vertical Depth: 1000'

Operator License No.: 6279
Op Name: PATRICK DEVELOPMENT CORPORATI
Address: 3408 W 93 RD
LEAWOOD, KS 66206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2012 8:00 AM
Plug Co. License No.: 33734 Plug Co. Name: HAT DRILLING LLC
Proposal Rcvd. from: ERIC STOGSDILL Company: HAT DRILLING LLC Phone: (620) 515-3823

Proposed Plugging Method: Mix and pump gel. Place a cement plug at TD and 550'. Circulate cement from 300' to surface.

Plugging Proposal Received By: RUSSELL HINE Witness Type: NONE
Date/Time Plugging Completed: 04/19/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Mix and pump gell down the drill stem at TD. Pumped 10 sacks of cement through the drill stem at TD. Pulled drill stem up to 582'. Pumped 10 sacks of cement through the drill stem at 582'. Pulled drill stem up to 300'. Pumped and circulated cement through the drill stem from 300' to surface. Pull the rest of the drill stem and topped the well off with cement. A total of 125 sacks of portland cement was used to plug this well.

Perfs:

RECEIVED
OCT 15 2012
KCC WICHITA

RECEIVED
OCT 10 2012
KCC Chanute Dist. #3

RD

Remarks:

Plugged through: DP

District: 03

Signed

[Signature]
10/19/12 (TECHNICIAN)