

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-20956-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 10-32S-8E
954 feet from S Section Line, 442 feet from E Section Line
Lease Name: M K AND O Well #: 3
County: CHAUTAUQUA Total Vertical Depth: 1788 feet

Operator License No.: 7288
Op Name: KLOBERDANZ, PAUL E.
Address: PO BOX 57756
OKLAHOMA CITY, OK 73157

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1788	700	75 SX
SURF	7	102		50 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/24/2012 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC. Phone: (405) 615-2323
Proposal Rcvd. from: PAUL E. KLOBERDANZ Company: _____

Proposed Plugging Method: SPOT 50' CMT PLUG ON BOTTOM, SHOOT CSG @ APPROXIMATELY 1000', PULL CASING, RUN 1" & SET 50' CMT PLUG @ 1000'; CIRCULATE CMT FROM 550' TO SURFACE.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 07/26/2012 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1725' gelled hole and spotted 5 sacks of cement. Pulled 1" out. Stretched casing and shot off at 700'. Pulled casing. Ran 1" to 700' and spotted 8 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 114 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1739	1744		
1734	1736		

RECEIVED

OCT 11 2012

KCC Chanute Dist. #3

DS

RECEIVED

OCT 18 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Paul A. Sims
10/29/12 (TECHNICIAN)