

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-21413-00-00
Spot: NWNEENE Sec/Twnshp/Rge: 15-32S-8E
4982 feet from S Section Line, 343 feet from E Section Line
Lease Name: MK AND O Well #: 6
County: CHAUTAUQUA Total Vertical Depth: 2650 feet

Operator License No.: 7288
Op Name: KLOBERDANZ, PAUL E.
Address: PO BOX 57756
OKLAHOMA CITY, OK 73157

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1740		
PROD	4.5	1957	800	75 SX
SURF	7	102		60 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/17/2012 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: PAUL E. KLOBERDANZ Company: _____ Phone: (405) 615-2323

Proposed Plugging Method: SPOT 50' CMT PLUG ON BOTTOM, SHOOT CSG @ APPROXIMATELY 1000', PULL CASING, RUN 1" & SET 50' CMT PLUG @1000'; CIRCULATE CMT FROM 550' TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 07/20/2012 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1725' gelled hole and spotted 5 sacks of cement. Pulled 1" out. Stretched casing and shot off at 800'. Pulled caing. Ran 1" to 800' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 125 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1746	1750		
1714	1726		

RECEIVED

OCT 11 2012

KCC Chanute Dist. #3

DS

RECEIVED

OCT 18 2012


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


10/20/12
(TECHNICIAN)