

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-095-22062-00-00  
 Spot: W2SWSW Sec/Twnshp/Rge: 24-27S-5W  
 660 feet from S Section Line, 330 feet from W Section Line  
 Lease Name: KERSCHEN Well #: 1-24  
 County: KINGMAN Total Vertical Depth: 4083 feet

Operator License No.: 5214  
 Op Name: LARIO OIL & GAS COMPANY  
 Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3700		
DVT		2447		130 SX CMT.
PKR		3730		
PROD	5.5	4073	1925	180 SX
SURF	8.625	292		180 SX
T1	2.375	3730		

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2012 12:00 AM  
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
 Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 297-3222

Proposed  
 Plugging  
 Method:

PER KCC REQUIREMENTS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL  
 Date/Time Plugging Completed: 09/21/2012 4:30 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3700' CAPPED WITH 2 SX CEMENT ON TOP. SANDED BACK TO 2200' CAPPED WITH 5 SX CEMENT. CUT CASING PIPE OFF @ 1925' PULLED CASING TO 900' SPOTTED 35 SX CEMENT. PULLED CASING TO 375'. CIRCULATED TO SURFACE WITH 125 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3794	3802		
3780	3784		
3770	3772		
3764	3766		
2338	2340		

RECEIVED  
 OCT 18 2012  
 10-18-12  
 KCC WICHITA

Remarks: QUALITY WELL SERVICE, 60/40 4% POS MIX, PUMPED CEMENT ALSO.

Plugged through: CSG

District: 02

Signed

*B. J. Hope*  
 10/20/12

(TECHNICIAN)