

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22052-00-00  
Spot: N2SWSWSW Sec/Twnshp/Rge: 4-28S-5W  
510 feet from S Section Line, 330 feet from W Section Line  
Lease Name: RAMSDALE Well #: 1-4  
County: KINGMAN Total Vertical Depth: 4111 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3763		
PROD	5.5	4103	2885	200 SX
SURF	8.625	252		185 SX
T1	2.375	3763		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2012 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 297-3222

Proposed Plugging Method: Per KCC recommendation.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/27/2012 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3716'-CAPPED WITH 5 SX CEMENT. CUT CASING PIPE OFF @ 2885' PULLED CASING TO 850' SPOTTED 35 SX CEMENT. PULLED CASING TO 375' CIRCULATED TO SURFACE WITH 130 SX CEMENT. CEMENT FELL INSIDE SURFACE CASING 160', 9-28-2012 TOPPED OFF WITH 65 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3778	3788		

RECEIVED  
OCT 18 2012  
KCC WICHITA

Remarks: QUALITY WELL SERVICE, 60/40 4% POS MIX, PUMPED CEMENT ALSO.

Plugged through: CSG

District: 02

Signed B. J. Hope  
10/25/12 (TECHNICIAN)