

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20179-00-00  
Spot: SENESEW Sec/Twnshp/Rge: 23-30S-40W  
2293 feet from S Section Line, 2631 feet from W Section Line  
Lease Name: BROWN GU E Well #: 2  
County: STANTON Total Vertical Depth: 2512 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2512	0	WITH 550 SX CMT
SURF	8.625	602		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2012 2:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 09/28/2012 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF TBG FISH @ 1086'. PUMP 50 SX CMT & 150# HULLS AT 1086'. TAG TOP OF CMT PLUG AT 614' WITH TBG. PUMP 66 SX CMT FROM 614' TO 0'. TOOH W/TBG. TOP OUT WITH 5 SX CMT. PUMP 60 SX CMT DOWN THE ANNULUS TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2424	2438		
2340	2376		
2255	2284		


Remarks: USED CLASS C COMMON CEMENY BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED  
OCT 18 2012  
KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED  
OCT 18 2012  
KCC WICHITA

