

To: 1.0770058 2-17
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

Operator License # 31938
Operator: Indian Oil Co., Inc.
Name: P.O. Box 209
Address: Medicine Lodge, KS 67104

~~15-007-01105-0000~~
API NUMBER 15-Drilled 1957 15-007-01105-0000
C NE NE, SEC. 1, T 35 S, R 13 W/E
4620 feet from S section line
660 feet from E section line
Lease Name Bartz-Platt Well # 1
County Barber 157.30
Well Total Depth 4840 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Quality Well Service License Number 31925
Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 10 a.m. Day: 17 Month: 2 Year: 19 98

Plugging proposal received from Richard McIntyre
(company name) Quality Well Service (phone) 316-727-3410

Work: 5 1/2" at 4840' with 200 sx cement, Perfs at 4796-4804, 4753-62'

- 1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer.
- 2nd plug at 600' with 50 sx cement,
- 3rd plug at 290' with 50 sx cement,
- 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 17 Month: 2 Year: 19 98


ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 5 sx cement on top of sand through bailer,

- 2nd plug pumped 10 sx gel and 50 sx cement at 600',
- 3rd plug pumped 5 sx gel and 50 sx cement at 290',
- 4th plug pumped 10 sx cement at 40'.

Good circulation.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2012' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 23 1998
INV. NO. 50109

Signed  (TECHNICIAN)