

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20852-00-00
Spot: CNWNENW Sec/Twnshp/Rge: 4-16S-19W
4950 feet from S Section Line, 1650 feet from W Section Line
Lease/Unit Name: OELKERS Well Number: 1
County: RUSH Total Vertical Depth: 3672 feet

Operator License No.: 31455
Op Name: C & L ENTERPRISES, INC.
Address: PO BOX 153
BAZINE, KS 67516

Conductor Pipe: Size _____ feet: 3 1/2
Surface Casing: Size 8.625 feet: 416
Production: Size 4.5 feet: 3671 WITH 225 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2002 2:30 PM
Plug Co. License No.: 32970 Plug Co. Name: H-D FIELD SERVICE, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D FIELD SERVICE, INC. Phone: (785) 398-2289

Proposed Plugging Method: SAND TO 3100' & 4 SX CMT. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/24/2002 4:10 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 3630'. PERFS AT 3346-48, 3372-74, 3403-06'. WELL SQUEEZED FROM 630-690' WITH 200 SX CMT BY ALLIED IN 1982. SANDED TO 3100' & 4 SX CMT. 1ST PLUG RUN TUBING TO 1258' & PUMP 50 SX CMT. 2ND PLUG PULL TUBING TO 650'. PUMP 140 SX CMT WITH 500# HULLS MIXED IN. CMT CIRCULATED. 3RD PLUG PULL TUBING AND TOPPED OFF WITH 10 SX CMT. HOLE STAYED FULL. TIED ONTO BACKSIDE AND PRESSURED UP TO 500#. HELD FOR 10 MINUTES.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

INVOICED JUN 25 2002

DATE 7-8-02
NO. 2003060020

Form OP-27