

1 030302

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,141-0000
NE, SEC. 4, T 16 S, R 19 W/EX
3300 feet from N SE Corner of W/EX section line
660 feet from W SE Corner of W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6302

Lease Name Victor Werth Well # 1

Operator: Stecklein Oil Company

County Rush

Name:

Address H-c # 32, Box 384

Well Total Depth 3635 118.14 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1260

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Stecklein Oil Company License Number 6302

Address H-C. # 32, Box 384, Hays, KS 67601

Company to plug at: Hour: 1:30 pm Day: 8 Month: October Year: 19 84

Plugging proposal received from Dan Stecklein

(company name) Stecklein Oil Co. (phone) 913-628-8850

were: 5 1/2" set at 3640' PBDT 3200' Perfs at 3496-3500'

1st plug sand back to 3200' and set CIBP

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Runout
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 pm Day: 8 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3640' PBDT 3200' Perfs at 3496-3500'

1st plug sanded back to 3200' and set CIBP, 2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in pressure 350 psi

OCT 12 1984

Remarks: They recovered 2500' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

VOICED
0-15-84
1322

Signed Steve Runout
(TECHNICIAN)