

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION **SE SW SE**, Sec. 14, T 16 S, R 19 W/W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,170-0000

330 feet from N/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Shuckman "A" Well # 1

Operator: **F & M Oil Co., Inc.**

County Rush

Name & **422 Union Center**

Address **Wichita, KS 67202**

Well Total Depth 3681 feet

Conductor Pipe: Size 119.63 feet

Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mustang Drilling & Exploration License Number 5652

Address Box 1425, Great Bend, KS 67360

Company to plug at: Hour: 8:45 pm Day: 18 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Gib Overbly

(company name) Mustang Drilling (phone) 316-262-2636

were: to fill hole with heavy mud. Circulate cement through drill pipe.

1st plug at 1260' with 50 sx cement

2nd plug at 840' with 50 sx cement

3rd plug at 390' with 40 sx cement

4th plug solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rathole with 10 sx cement.

Signed Steve Vincent  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:00 am Day: 19 Month: January Year: 19 84

ACTUAL PLUGGING REPORT to fill hole with heavy mud. Spot cement through drill pipe.

1st plug at 1260' with 50 sx cement, 2nd plug at 840' with 50 sx cement, 3rd plug at

390' with 40 sx cement, 4th plug solid bridge 5th plug hulls - plug at 40' -- cement

to surface with 10 sx cement. 6th plug to circulate rathole with 10 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. by Sun Cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (~~xxx~~ / did not) observe this plugging.

Signed Steve Vincent  
(TECHNICIAN) ✓

INVOICED RECEIVED  
STATE CORPORATION COMMISSION  
DATE 1-26-84 JAN 23 1984  
INV. NO. 9254-6  
CONSERVATION DIVISION  
Wichita, Kansas  
1-19