

To: **1090550** **5-27**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,883-0000  
S/2 SW NW, SEC. 11, T. 20 S, R. 23 W/EX  
2310 feet from NE section line  
660 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31231  
Operator: Hyde-Marrs, Inc./American Energies  
Name & Address: 155 N. Market, Ste. 710  
Wichita, KS 67202

Lease Name Reinert Well # 1  
County Ness 143.65  
Well Total Depth 4420 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 453

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mallard JV, Inc. License Number 4958

Address P.O. Box 1009, McPherson, KS 67460-1009

Company to plug at: Hour: 9 a.m. Day: 27 Month: 5 Year: 19 95

Plugging proposal received from Carol

(company name) Mallard JV, Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1480'

1st plug at 1480' with 50 sx cement, 2nd plug at 660' with 40 sx cement,

3rd plug at 490' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:45 a.m. Day: 27 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 1480' with 50 sx cement,

2nd plug at 660' with 40 sx cement,

3rd plug at 490' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

**INVOICED**

Signed [Signature]  
(TECHNICIAN)

DATE JUN 13 1995

INV. NO. 42953  
5-7

EFFECTIVE DATE: 5-15-95

State of Kansas

135-23,883-0000

ALL BLANKS MUST BE FILLED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

SGA? ... Yes ...  No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 5 22 95  
month day year

Spot 872 SW - NW Sec 11 Twp 20 S, Rg 23 East  
 West

OPERATOR: License # 31231  
Name: (Hyde-Marrs, Inc.) & American Energies Corp  
Address: 155 North Market, Suite 710  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Thomas C. Hyde  
Phone: 316-262-8339

2310 feet from South / North line of Section  
660 feet from East / West line of Section  
CORP'S SECTION  REGULAR  IRREGULAR?

CONTRACTOR: License # 4958  
Name: Mallard JV, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Neosho

Lease Name: Reinert Well # 1  
Field Name: \_\_\_\_\_

Is this a Prorated/Spaced Field? ... yes  no

Target Formation(s): Cherokee Sand

Nearest lease or unit boundary: 660

Ground Surface Elevation: 2246 feet MSL

Water well within one-quarter mile: ... yes ... no

Public water supply well within one mile: ... yes  no

Depth to bottom of fresh water: 350

Depth to bottom of usable water: 550

Surface Pipe by Alternate: ... 1  2

Length of Surface Pipe Planned to be set: 440

Length of Conductor pipe required: \_\_\_\_\_

Projected Total Depth: 4450

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:

... well  farm pond ... other

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal  Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
... Other \_\_\_\_\_

If OWWO: old well information as follows:

Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_

Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes  no

If yes, true vertical depth: \_\_\_\_\_

Bottom Hole Location: \_\_\_\_\_

Will Cores Be Taken? ... yes  no

If yes, proposed zone: \_\_\_\_\_

380' Alt. II Req.

Exp. 11/10/95

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

Pusher Carol INIT. RL

SPUD DATE 5-20-95

LENGTH SURFACE PLANNED 440 of 854

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD?  Y  N SIZE HOLE \_\_\_\_\_

SURFACE PIPE 8 1/2 @ 453 CONDUCTOR \_\_\_\_\_

ANHYDRITE T- B-1480 ELEVATION \_\_\_\_\_

TD 4420 FORMATION \_\_\_\_\_

RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
SX Y N

Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Anhydrite Base @ 1480 Ft. W/ 50 SX

1/2 Base Anhy. @ 680 Ft. W/ 40 SX

1/2, 1/2 Plug @ 490 Ft. W/ 50 SX

Bottom Surface @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/10 SX

WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)

TECHNICIAN SM DATE 5-22-95 Hauling \_\_\_\_\_

TYPE OF CEMENT 60/40 67 1/2

STARTING TIME 9: (AM/PM) DATE 5-27

COMPLETION TIME 10:45 (AM/PM) DATE 5-27

CEMENT COMPANY Helmed