

1 060075

5-10

59 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- 135-23,572-0000
SW NW NW, SEC. 11, T 20 S, R 23 W/E

4290 feet from S section line

4950 feet from E section line

Lease Name Reinert Well # 1

County Ness 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 310

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Operator: Bankoff Oil Company
Name & Address: 100 S. Market, Suite 203 A
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 10 Month: 5 Year: 19 91

Plugging proposal received from Jay Schneider

(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1453-85'

1st plug at 1500' with 50 sx cement, 2nd plug at 900' with 80 sx cement,

3rd plug at 340' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11 p.m. Day: 10 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 900' with 80 sx cement,

3rd plug at 340' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floeal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-22-91

WIK. NO. 31862

MAY 15 1991

Signed [Signature] (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Expected Spud Date 4 month 22 day 91 year

SW. NW. NW Sec 11. Twp 20. S, Rg 23. East West

OPERATOR: License # 6040
 Name: Bankoff Oil Company
 Address: 100 S. Market, #203 A
 City/State/Zip: Wichita, KS 67202
 Contact Person: Frank S. Mize
 Phone: 316-262-2784

4290 feet from South line of Section
4950 feet from East line of Section
 (Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5929
 Name: Duke Drilling

County: Ness
 Lease Name: Reinert Well #: 1
 Field Name: McCreight
 Is this a Prorated Field? yes no
 Target Formation(s): Mississippian
 Nearest lease or unit boundary: 330'
 Ground Surface Elevation: 2241 feet MSL
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no
 Depth to bottom of fresh water: 100
 Depth to bottom of usable water: 725
 Surface Pipe by Alternate: 1 1 2
 Length of Surface Pipe Planned to be set: 300'
 Length of Conductor pipe required: 0
 Projected Total Depth: 4450'
 Formation at Total Depth: Mississippian
 Water Source for Drilling Operations: well farm pond other
 DWR Permit #: contractor will file
 Will Cores Be Taken?: yes no
 If yes, proposed zone: _____

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OAWO Disposal Wildcat Cable
 Seismic; # of Holes _____

If OAWO: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth: _____

Directional, Deviated or Horizontal wellbore? yes no
 If yes, total depth location: _____

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 15 1991

Exp. 10/20/91

CONSERVATION DIVISION AFFIDAVIT

250' Alt. II Req.

The undersigned hereby affirms that the well is being completed and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
 It is agreed that the following minimum requirements will be met:

Pusher JAY
 SPUD DATE MAY 3, 1991 INIT. GB
 LENGTH SURFACE PLANNED 300' of 8 1/2"
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE _____
 SURFACE PIPE 8 1/2" @ 3/0 CONDUCTOR _____
 ANHYDRITE T- 1452 B- 1465 ELEVATION _____
 TD 4400 FORMATION _____
 RAN PIPE @ SX DV TOOL SX ALT II DONE SX Y N
 _____ Arbuckle Plug @ _____ Ft. W/ _____ SX
 _____ Hug./Council @ _____ Ft. W/ _____ SX
 _____ Anhydrite Base @ 1500 Ft. W/ 50 SX
 _____ 1/2 Base Anyh. @ 900 Ft. W/ 80 SX
 _____ 1/2, 1/2 Plug @ _____ Ft. W/ 50 SX
 _____ Bottom Surface @ 340 Ft. W/ 50 SX
 _____ 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 5 SX MOUSE HOLE W/ _____ SX
 WATER WELL _____ SX (Irr. Well _____ Pond _____)
 TECHNICIAN cm DATE 5-9-91 Hauling _____
 TYPE OF CEMENT 60/40 67. 1/4 # FL/50K
 STARTING TIME 9:00 (AM/PM) DATE 5-10-91
 COMPLETION TIME 11:00 (AM/PM) DATE 5-10-91
 CEMENT COMPANY Allied