

To: 1 060770  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,982 - 0000

W/2 SE SW, SEC. 30, T 20 S, R 25 W/E  
660 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6574

Lease Name Slagle Well # 1

Operator: Bird Energy, Inc.  
Name & Address: Box 1612  
Dodge City, KS 67801

County Ness 144.30  
Well Total Depth 4440 Mississippi feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor JW Drilling Co., Inc. License Number 5137

Address 200 E. First, Suite 500, Wichita, KS 67203

Company to plug at: Hour: 7:00 am Day: 17 Month: January Year: 19 86

Plugging proposal received from Bill Roach

(company name) JW Drilling (phone) 316-263-5705

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1600'  
Elevation 2293

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug at the base of the Dakota with 50 sx cement

4th plug 30' below the base of the surface pipe with 50 sx cement  
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi  
cement to surface with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 15 sx cement  
Plugging Operations attended by Agent: All Part None X

Operations Completed: Hour: 9:45 am Day: 17 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1630' with 50 sx cement, 2nd plug at 1345' with 80 sx

cement, 3rd plug at 570' with 50 sx cement, 4th plug at 290' with 50 sx cement, 5th

and 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

7th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan  
(if additional description is necessary, use BACK of this form.)

INVOICED  
did not observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE JAN 29 1986  
INV. NO. 12156

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: Jan. 20 1986  
month day year

API Number 15- 135-22,982 - 0000  
W/2 SE SW Sec. 30 Twp. 20 S. Rge. 25  
 East  West  
(location)

OPERATOR: License # 6574  
Name Bird Energy, Inc  
Address Box 1612  
City/State/Zip Dodge City, Ks 67801  
Contact Person Louis S. Bird  
Phone 316 227.6041

660 Ft North from Southeast Corner of Section  
3630 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5137  
Name JW Drilling Co., Inc  
City/State Wichita, Kansas

Nearest lease or unit boundary line 660 feet.  
County Ness  
Lease Name Slagle Well# 1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 100 feet  
Lowest usable water formation Dakota  
Depth to Bottom of usable water 500 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set 240 feet  
Conductor pipe if any required feet  
Ground surface elevation feet MSI.

If OWWO: add well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 4400 feet  
Projected Formation at TD Miss  
Expected Producing Formations Miss

This Authorization Expires 6-10-86  
Approved By 12-10-85

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

12-9-85 Signature of Operator or Agent *Louis S. Bird* Title President  
*More in 1-10-86 8 5/8 at 240'* Form C-1 4/84 *110*

STATE OF KANSAS

JAN 27 1986

CONSERVATION DIVISION  
Wichita, Kansas

PUSHER Bell, Roch

TD 4440 FORMATION Miss

SURFACE PIPE 2 5/8" x 259'

ANHYDRITE 1000 ELEVATION 2293

STARTING TIME & DATE 1-14-86

COMPLETION TIME & DATE 2:44 PM 1-17-86

1st PLUG @ 1630 FT. W/ 50 SX

2nd PLUG @ 1345 FT. W/ 80 SX

3rd PLUG @ 577 FT. W/ 50 SX

4th PLUG @ 290 FT. W/ 50 SX  
*40-1054 sub.*

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/      SX

WATER WELL PLUGGED W/      SX

CEMENT COMPANY B S Tilton

TECHNICIAN     

*1st anhyd w/ 50*  
*2nd Chryse w/ 80*  
*3rd Dakota w/ 50*  
*4th 3.0' out w/ 50*  
*577 40 - 13 w/ 10*  
*cu 15 -*  
*60/40 w/ 6% salt*