

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22783-00-00
Spot: NWSE Sec/Twnshp/Rge: 10-35S-35W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MERRILOY Well #: 3-10
County: STEVENS Total Vertical Depth: 1000 feet

Operator License No.: 5263
Op Name: MIDWESTERN EXPLORATION COMPA
Address: 3500 S BOULEVARD STE 2B
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	40		

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 10/13/2012 12:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: BILLY DOUGHERTY Company: MIDWESTER EXPLORATION Phone: (405) 340-4300

Proposed Plugging Method: 1ST PLUG AT 620' WITH 100 SX CMT. 2ND PLUG AT 300' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 150 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 10/13/2012 3:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PRIOR TO PLUG PUMP DOWN CONDUCTOR PIPE WITH 200 SX CMT. HOLE ON VACUUM. LOST CIRCULATION FROM 500'-1000'. COULDN'T GET PAST 500' DUE TO HOLE CAVING IN. 1ST PLUG AT 620' WITH 200 SX CMT. 2ND PLUG AT 300' WITH 200 SX CMT. 3RD PLUG AT 40' WITH 230 SX CMT TO SURFACE. 4TH PLUG TO CIRCULATE RAT HOLE WITH 75 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 30 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED
OCT 25 2012
KCC WICHITA

District: 01

Signed

Steve Pfeifer
11/08/12 (TECHNICIAN)

RECEIVED
OCT 25 2012
KCC DODGE CITY

AW7