

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22809-00-00
Spot: SENEENE Sec/Twnshp/Rge: 31-12S-21W
600 feet from N Section Line, 270 feet from E Section Line
Lease Name: HILLMAN-DUBACH Well #: 1-31
County: TREGO Total Vertical Depth: 4048 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/08/2012 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 10/08/2012 12:00 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st plug @4000 w/25 sx
2nd plug @1725 w/25 sx
3rd plug @925 w/100 sx
4th plug @270 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED
NOV 02 2012
KCC WICHITA

District: 04

Signed

Bruce D. Basye
10/08/12 (TECHNICIAN)

CM