

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21827-00-01
Spot: SWNENWSW Sec/Twnshp/Rge: 27-31S-34W
2027 feet from S Section Line, 4421 feet from E Section Line
Lease Name: FEDERAL FARM MORTGAGE Well #: 3
County: SEWARD Total Vertical Depth: 5800 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 5250 | | |
| CIBP | | 5600 | | WITH 2 SX CMT |
| PC | | 3187 | | WITH 60 SX CMT |
| PROD | 5.5 | 5800 | 1895 | WITH 260 SX CMT |
| SURF | 8.625 | 1746 | | WITH 660 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/29/2012 2:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580)254-1881

Proposed Plugging Method: CIBP @ 5250' WITH 2 SX CMT. PUMP 300# HULLS & 25 SX CMT AT PERFS. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2012 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5250'. PUMP 600# HULLS & 25 SX CMT TO 4760'. PRESSURE TO 450#. HOLDING. 1ST PLUG AT 1807' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|---------------|
| 5624 | 5640 | | ST LOUIS |
| 5296 | 5305 | | MORROW |
| 4754 | 4760 | | MARMATON, LOW |
| 4691 | 4696 | | MARMATON, UPP |


Remarks: USED PORTLAND COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED
NOV 05 2012
KCC WICHITA

District: 01

Signed


10/30/12

(TECHNICIAN)

ARCS