

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20322-00-00
Spot: N2N2NW Sec/Twnshp/Rge: 23-19S-29W
4967 feet from S Section Line, 3936 feet from E Section Line
Lease Name: MUMMA FARMS A Well #: 1
County: LANE Total Vertical Depth: 4650 feet

Operator License No.: 32322
Op Name: DENIS F. ROBERTS
Address: 3904 FAIRWAY DR BOX 1252
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4180		WITH 2 SX CMT
PROD	4.5	4649	0	WITH 150 SX CMT
SURF	8.625	281		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2012 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 4180' & 2 SX CMT. PERFORATE @ 2185'. PUMP HULLS & 50 SX CMT. PERFORATE @ 1300' WITH 80 SX CMT OVER CASING VOLUME. 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2012 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4180' WITH 2 SX CMT. PERFORATE @ 2185' & 1375'. PUMP 50 SX CMT WITH 100# HULLS AT 2200' THROUGH TBG. HOLE CIRCULATED UP 4 1/2" CASING. TOOH W/TBG. TAKE INJECTION RATE DOWN 4 1/2" CASING 2 BPM @ 500#. MIX & PUMP 70 SX CMT, 100# HULLS THEN 70 SX CMT. PRESSURE 4 1/2" CASING FROM 200# TO 400#. NO BLOW OR CIRCULATION UP 4 1/2" X 8 5/8" ANNULUS. HOOK TO 4 1/2" X 8 5/8" ANNULUS & PUMP 20 SX CMT. PRESSURE TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
4235	4238		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
10/22/12 (TECHNICIAN)

RECEIVED
OCT 31 2012
KCC DIVISION CITY

RECEIVED
NOV 05 2012
KCC WICHITA

AWY