

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22195-00-00
Spot: E2NENENW Sec/Twnshp/Rge: 6-18S-30W
332 feet from N Section Line, 2329 feet from W Section Line
Lease Name: BAIER-CURRAN UNIT Well #: 1-6
County: LANE Total Vertical Depth: 4610 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4220		WITH 2 SX CMT
CIBP		4344		WITH 2 SX CMT
DVT		2326		WITH 600 SX CMT
PROD 4.5		4576	0	WITH 280 SX CMT
SURF 8.625		309		WITH 205 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/16/2012 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LARRY KARLIN Company: LARIO OIL & GAS Phone: (620) 805-1300

Proposed Plugging Method: SET CIBP @ 4344' WITH 2 SX CMT. SET CIBP @ 4220' WITH 2 SX CMT. PLUG AT 2250' WITH 15 SX GEL & 25 SX CMT. PLUG AT 1250' CIRCULATE CMT TO SURFACE. CHECK BACKSIDE TO 300# WITH 50 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2012 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4344' WITH 2 SX CMT. CIBP @ 4220' WITH 2 SX CMT. 1ST PLUG AT 2250' WITH 15 SX GEL & 15 SX CMT. 2ND PLUG AT 1250' WITH 85 SX CMT. CMT TO SURFACE. PULL TBG & TOP OFF WITH 10 SX CMT. TIE ONTO BACKSIDE & PUMP 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4394	4402		
4270	4276		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed


11/08/12
(TECHNICIAN)

RECEIVED
NOV 05 2012
KCC WICHITA