

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20043-00-02  
Spot: SWSW Sec/Twnshp/Rge: 35-32S-31W  
660 feet from S Section Line, 660 feet from W Section Line  
Lease Name: GANO A Well #: 2  
County: SEWARD Total Vertical Depth: 6020 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5000		WITH 2 SX CMT
DVT		3370		
PROD	5.5	6019	2400	WITH 475 SX CMT
SURF	8.625	1600		WITH 800 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/29/2012 11:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: CIBP @ 5000' WITH 2 SX CMT. PLUG AT 1650' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/29/2012 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 1653' WITH 50 SX CMT. 2ND PLUG AT 561' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5913	5916		
5083	5087		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Ken Jehlik  
11/08/12 (TECHNICIAN)

RECEIVED  
NOV 05 2012  
KCC WICHITA