

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21435-00-01
Spot: NENWNESE Sec/Twnshp/Rge: 4-32S-33W
2327 feet from S Section Line, 779 feet from E Section Line
Lease Name: JARRETT TRUST Well #: 1-4
County: SEWARD Total Vertical Depth: 5949 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5450		WITH 2 SX CMT
PC		3005		UNCEMENTED
PROD 4.5		5948	1822	WITH 220 SX CMT
SURF 8.625		1796		WITH 700 SX CMT

Well Type: SWD UIC Docket No: D27209.0 Date/Time to Plug: 10/24/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0806

Proposed Plugging Method: CIBP @ 5450' WITH 2 SX CMT. PLUG AT 1820' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2012 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5450' WITH 2 SX CMT. 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5880	5890		
5754	5758		
5702	5758		
5512	5522		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed [Signature] (TECHNICIAN)

cc to KCC (11/06/12)

RECEIVED
NOV 05 2012
KCC WICHITA