

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20149-00-02
Spot: S2S2NW Sec/Twnshp/Rge: 5-24S-16W
2335 feet from N Section Line, 1327 feet from W Section Line
Lease Name: MITCHELL Well #: 1
County: EDWARDS Total Vertical Depth: 4290 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2525		WITH 2 SX CMT
CIBP		2650		
CIBP		4110		WITH 2 SX CMT
PROD	4.5	4288	0	WITH 375 SX CMT
SURF	8.625	322		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/26/2012 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: SHANE PELTON Company: HERMAN L. LOEB LLC Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP @ 4110' WITH 2 SX CMT. SET CIBP @ 2530' WITH 2 SX CMT. RUN BOND LOG. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2012 1:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4110' WITH 2 SX CMT. SET CIBP @ 2525' WITH 2 SX CMT. RAN BOND LOG. TOC @ 630'. PERFORATE @ 600'. CIRCULATED CMT TO SURFACE WITH 215 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4169	4190		
2597	2604		
2582	2588		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
NOV 05 2012
KCC WICHITA

District: 01

Signed Eric MacLaren By Richard Lacey
11/08/12 (TECHNICIAN)