

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20674-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 20-22S-3W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: SCHMIDT Well #: 1
County: HARVEY Total Vertical Depth: 2600 feet

Operator License No.: 7116
Op Name: KANTOR OIL COMPANY, LLC
Address: 15 W 6TH ST STE 2601
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2568		
PROD	5.5	2600	609	150 SX
SURF	13.375	240		350 SX
T1	2.375	2550		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2012 12:00 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: LARRY RESSLER Company: _____ Phone: (620) 664-0597

Proposed
Plugging
Method:

PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 10/24/2012 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2425' - CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 609' PULLED CASING TO 517' SPOTTED 35 SX CEMENT. WAITED 2 HOURS TAG TOP OF CEMENT @ 411'. PULLED CASING TO 300' CIRCULATED TO SURFACE WITH 210 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
2533	2534		

RECEIVED
NOV 06 2012
KCC WICHITA

Remarks: CONSOLIDATED OUT OF EL DORADO, 70/30/4%- CC POS MIX, TICKET #35332, HAD NOT PRODUCED FOR 5 YEARS.

Plugged through: CSG

District: 02

Signed B. J. Hope
10/28/12 (TECHNICIAN)