

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20990-00-00
Spot: SWNWNESE Sec/Twnshp/Rge: 17-25S-1E
2198 feet from S Section Line, 991 feet from E Section Line
Lease Name: HALEY Well #: 2-A
County: SEDGWICK Total Vertical Depth: 3342 feet

Operator License No.: 6804
Op Name: LACHENMAYR OIL LLC
Address: PO BOX 526
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3020		
CIBP		3164		
PROD	5.5	3342	1693	225 SX
SURF	8.625	201		120 SX
T1	2.875	2616		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2012 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND BACK TO 2950' AND CAP WITH 5 SX OF CEMENT BACK TO 2950'. PERF AT 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2012 1:00 AM KCC Agent: BRANDON MILNER

Actual Plugging Report:

SANDED BACK TO 2936' AND CAPPED WITH 5 SX OF CEMENT. CASING SHOT OFF AT 1693'. CASING WAS THEN PULLED TO 250' AND 125 SX WAS CIRCULATED THROUGH CASING TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3004	3013	CSG	
2680	2682	CSG	KC-SQZ
2642	2644	CSG	KC-SQZ
2640	2642	CSG	

RECEIVED
NOV 06 2012
KCC WICHITA

Remarks: QUALITY WELL SERVICE TICKET #5570

Plugged through: CSG

District: 02

Signed Brandon Milner
11/08/12 (TECHNICIAN)