

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21653-00-00
Spot: NESWNE Sec/Twnshp/Rge: 36-10S-17W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WHISMAN Well #: 6
County: ROOKS Total Vertical Depth: 3540 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3538		250 sx
SURF	8.5	206		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2012 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JOHN M CALLEN Company: EDMISTON OIL CO INC. Phone: (620) 793-2672

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls
Perforated at 250', 650', 1142' and 1842'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2012 11:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2300' and pumped 75 sx cement.
Pulled tubing to 1850' and pumped 210 sx cement w/150 # hulls to circulate cement to surface.
Pulled all tubing. Hooked to 4 1/2" casing and pumped 30 sx cement to circulate 8 5/8" x 4 1/2" annulus to surface. Shut in annulus and pressured 4 1/2" casing to 200 psi. Shut in pressure 200 psi.

GPS: 39.14268N, -099.16467W

Perfs:

Top	Bot	Thru	Comments
3380	3420		
3136	3336		
3082	3082		

RECEIVED
NOV 07 2012
KCC WICHITA

Remarks: CONSOLIDATED TICKET # 37271

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

NOV 02 2012