

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20952-00-00
Spot: SWNWSWNW Sec/Twnshp/Rge: 3-9S-16W
3351 feet from S Section Line, 5260 feet from E Section Line
Lease Name: GAMBLE Well #: AW4
County: ROOKS Total Vertical Depth: 3825 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3325		
PROD	4.5	3368		900 SX
SURF	8.58	122		80 SX
TI	2.375	3012		

Well Type: [REDACTED] UIC Docket No: E07166.2 Date/Time to Plug: 10/05/2012 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Packer stuck in hole @ 3012'.
4 1/2" casing cemented top to bottom.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2012 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2725' and pumped 100 sx cement w/150 # hulls.
Pulled tubing to 1386' and pumped 90 sx cement to circulate to surface.
Pulled all tubing. Hooked to 4 1/2" casing and pumped 25 sx cement.
Shut in pressure 800 psi.
Hooked to 8 5/8"x4 1/2" annulus. Pressured immediately. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3180	3184		
3168	3170		
3136	3142		
3104	3184		

RECEIVED
NOV 07 2012

KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING TICKET # 39141

Plugged through: TBG

District: 04

Signed

Pat Bedore
10/08/12
(TECHNICIAN)

CM

OCT 19 2012