

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24053-00-00
Spot: NESWNWSW Sec/Twnshp/Rge: 19-10S-20W
1705 feet from S Section Line, 4651 feet from E Section Line
Lease Name: ROMINE SW Well #: 5
County: ROOKS Total Vertical Depth: 3832 feet

Operator License No.: 33933
Op Name: ANCHOR BAY PETROLEUM LLC
Address: 2713 ASH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3830		150 SX
SURF	8.625	204		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2012 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ED GLASMAN Company: ANCHOR BAY PETROLEUM, LLC Phone: (785) 259-5807

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Arbuckle perms: 3759' - 3780'.
Kansas City perms: 3641' - 3647'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2012 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Sanded bottom to 3600', bail dumped 5 sx cement.
Pioneer shot 5 1/2" casing off @ 2312', Pulled 5 1/2" casing to 2050' and pumped 110 sx cement w/300 # hulls.
Pulled casing to 1650' and pumped 40 sx cement w/50 # hulls.
Pulled casing to 900' and pumped 40 sx cement w/50 # hulls.
Pulled casing to 204' and pumped 55 sx cement w/100 # hulls to circulated cement to surface.
Pulled 5 1/2" casing. Topped off 8 5/8" casing with 15 sx cement.
GPS: 39.16652N, -099.60300W

Perfs:

Top	Bot	Thru	Comments
3759	3780		
3641	3647		

Remarks: QUALITY OILWELL CEMENTING TICKET # 6161

Plugged through: CSG

District: 04

Signed

Pat Bedore
11/08/12 (TECHNICIAN)

CM

NOV 02 2012

RECEIVED
NOV 07 2012
KCC WICHITA