

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22761-00-00  
Spot: W2NESE Sec/Twnshp/Rge: 5-15S-18W  
1980 feet from S Section Line, 990 feet from E Section Line  
Lease Name: MUNSCH Well #: 2  
County: ELLIS Total Vertical Depth: 3620 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 300 W DOUGLAS AVE, STE 410  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3618		215 SX
SURF	8.625	385		215 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/26/2012 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TERRY PIESKER Company: ANDERSON ENERGY INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/500 # hulls and 8 sx gel. Perforations: 3452' - 3460', 3476', 3431', 3033', 3593' - 3598'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/26/2012 11:15 AM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Perforated @ 1650', 1204', and 562'.  
Ran in hole with tubing to 3512' and pumped 8 sx gel followed by 50 sx cement w/100 # hulls.  
Pulled tubing to 1650'. Rigged to tubing and pumped 137 sx cement w/200 # hulls to circulate cement to pit area.  
Pulled tubing. Topped off 4 1/2" casing with 10 sx cement. Hole standing full.  
Rigged to 8 5/8" casing. Pumped 3 sx cement. Cement blew out top of head. Backside full.  
GPS: 38.77504 -099.34090


**Perfs:**

Top	Bot	Thru	Comments
3593	3598		
3476	3476		
3452	3460		
3431	3431		
3033	3033		

Remarks: ALLIED OIL AND GAS SERVICES TICKET # 53585

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)  
10/26/12

CM

RECEIVED  
NOV 07 2012  
KCC WICHITA

2012 10 29