

1070834

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,437-0000

W/2 SE NE, SEC. 11, T 20 S, R 23 W/E
3300 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30080

Lease Name Foos Well # 1

Operator: Honey Oil Company
Name & Address: 401 E. Douglas, Suite 505
Wichita, KS 67202

County Ness 143.65

Well Total Depth 4420 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 447

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address Ness City, KS

Company to plug at: Hour: 9:15 a.m. Day: 6 Month: 8 Year: 19 90

Plugging proposal received from Max Parsons

(company name) Plains, Inc. (phone) 913-798-3995

were: 5 1/2" at 4119' w/125 sx cement, PRTD 4378', Perfs at 4252-4356'

1st plug pump 200 lbs. hulls and 25 sx cement,

2nd plug perforate at 700', pump cement to circulate on backside.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 6 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement,

2nd plug perforated at 700' and pumped 280 sx cement down 5 1/2", cement circulated to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE: AUG 23 1990

Signed Dan Johnson (TECHNICIAN)

INV. NO. 29016