

1 070171

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,399-0000
SW NE, SEC. 11, 'T 20 S, R 23 WXS
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033
Operator: Murfin Drilling Company
Name & Address 250 N. Water, Suite 300
Wichita, KS 67202

Lease Name Foos Well # 1
County Ness 141.77
Well Total Depth 4362 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 447

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 1:50 pm Day: 15 Month: April Year: 1986

Plugging proposal received from Mike Ward

(company name) Murfin (phone) 316-267-3241

were: 4 1/2" at 4418' PBD 4356' Perfs at 4251-55'

1st plug pump 30 sx cement to bottom through tubing.

2nd plug fill hole with gelled water - shoot casing at 900' and pump 175 sx cement (don't displace cement from casing. If cement does not circulate have 100 sx cement on location to pump down annulus).

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 pm Day: 15 Month: April Year: 1986

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement at 4261' through tubing. 2nd plug pumped 18 sx gel. Circulated through tubing from 4250 to 800'. Perforated at 900', pulled tubing, pumped 260 sx cement through 4 1/2". Circulated approximately 30 bbls mud out 8 5/8". Pumped 15 sx cement down 8 5/8"

STATE CORPORATION COMMISSION
APR 28 1986
CONSERVATION DIVISION
Wichita, Kansas

Remarks: No recovery. Used 60/40 Pozmix 6% gel 3% cc by Halliburton.
(If additional description is necessary, use BACK of this form.)

(I did not observe this plugging.)

Signed Dan Godwin
(TECHNICIAN)

DATE APR 29 1986

INV. NO. 13593