

1 030518

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,897-0000R

C E/2 NE NW, SEC. 18, T 20 S, R 23 W/R
4620 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5601 Lease Name Edwin Carlson Well # 1

Operator: Associated Petroleum Consultants, Inc. County Ness 145.60
Name & Address One Main Place, Suite 600
Wichita, KS 67202
Well Total Depth 4480 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 534

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 16 Month: September Year: 19 85

Plugging proposal received from Tony Martin

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1590-1571'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 600' with 50 sx cement
solid bridge

3rd plug hulls + plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 am Day: 16 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement, 2nd plug at 600' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (date) did not observe this plugging.

DATE SEP 24 1985

Signed Alex N...
(TECHNICIAN)

INV. NO. 10218